

BILL OF QUANTITIES FOR KWA KIOKO MAJOR GULLEY CURING INITIATIVES BY GABIONS INSTALLATION					
All prices are inclusive of indirect labour costs, profits & overheads					
Bill A	Gabion Works				
Item No.	Item Description	Unit	Qty	Rate Kshs.	Amount Kshs.
Carry out the following works for the gabion lining. Rate to include delivery of hardcore beyond access point to site, preparation for the base surface.					
1.01	Mobilization of materials and artisans, including setting up camp and demobilization	LS			
1.02	Supply and lay/install 2 m*1 m*1 m high gauge gabion boxes and pack with approved hardcore. Rate inclusive of preparation for the base surface/ foundation and grouting as shall be instructed	LS	42		
1.03	Provide hardcore and package closely with minimal void spaces as specified in the drawing and instructions from the supervising engineer	Tons	84		
1.04	Earth material fill to the space between the culvert and the gabions installation point	M ³	200		
Sub Total					
BILL B	Provisional Sums				
1	Allow a provisional sum of Kshs. 40,000.00 for contingencies to be expended at the discretion of the project manager	LS			40,000
2	Allow a provisional sum of Kshs. 25,000.00 for technical supervision	LS			25,000
Sub Total					
GRAND SUMMARY					
Bill A	GABION WORKS				
Bill B	PROVISIONAL SUMS				
	Total				
	Add VAT (16%)				
	<u>Grand Total Carried to Form of Tender</u>				