



Fadhili Trust

P.O. Box 244 - 00511,
Ongata Rongai.

Tel: +254 710 401 208
+254 733 867 112

Email: info@fadhilitrust.org
Web: www.fadhilitrust.org

REQUEST FOR QUOTATION FOR CONSTRUCTION OF INTAKE/SILT TRAPS (CHAMBERS), DAM LINERS & SHADE NETTING INSTALLATION FOR 25 FARM PONDS IN MBUI NZAU, MIKUYUNI & KALUNGU SUB-LOCATIONS, KIBWEZI EAST SUB-COUNTY

1. Introduction

Fadhili Trust invites qualified and experienced suppliers to submit quotations for the **construction of intake/silt traps (chambers), dam liners & shade netting installation for 25 farm ponds in Mbui Nzau, Mikuyuni & Kalungu sub-locations, Kibwezi East Sub-County**. The farm ponds have already been dug, and dam liners & shade nets have been supplied. The scope includes supplying and installing all additional necessary equipment for operationalizing the farm ponds as per the provided bill of quantities.

2.0 Quotation Requirements

Interested companies MUST provide the following:

- A completed and stamped **Bill of Quantities** (as per the table below).
- A detailed **Company Profile** including:
 - i. Certificate of Registration/Incorporation.
 - ii. Valid Tax Compliance Certificate.
 - iii. Business Permit.
 - iv. Evidence of similar work conducted (e.g., contracts, completion certificates, reference letters).
 - v. Detailed Work Plan (including timelines and methodology for the project).

3.0 Submission Details

- Completed quotations and supporting documents MUST be submitted via email to: procurement@fadhilitrust.org & info@fadhilitrust.org
- Deadline for submission: **16th October 2025, 3:00 PM**

4.0 Terms of payment

Payment to the contractor will be made in milestones as follows

- 50% will be paid after mobilization of equipment, technical staff, signing of the contract, and submission of an inception report.
- 45 % after satisfactory completion of all farm ponds work as per the bill of quantities, and presentation of progress reports.
- 5 % will be held as a retention for a Defects Liability Period of **three months** to take care of any defects



Fadhili Trust

P.O.Box 244 - 00511,

Ongata Rongai.

Tel: +254 710 401 208

+254 733 867 112

Email: info@fadhilitrust.org

Web: www.fadhilitrust.org

5.0 Bill of Quantities

BILL OF QUANTITIES FOR CONSTRUCTION OF INTAKE/SILT TRAPS (CHAMBERS), DAM LINERS & SHADE NETTING INSTALLATION

S/No.	Description of Work/Material	Unit	Quantity	Rate (KES)	Total (KES)
1.0	Preliminary Works				
1.01	Mobilization and transportation of equipment, tools, and materials.	LS	1		
2.0	Carry out farm pond auxiliary works: ~				
	Carry out Shade Netting Installation as follows: ~				
2.0.1	Supply and install 80 m Length, 3mm dia/thick galvanized wire or plain wire on anchored metal pegs (hold & suspend shade net)	m	80		
2.0.2	Anchoring Pegs, Rebars D16mm X 0.45m long sections, 2.5m spacing	Kg	15.8		
2.0.3	Allow for farm pond lining 10m x 10m x 2m (Pond Liners provided), inclusive of shaping of the slopes	LS	1		
	Sub Total (Carried to Collection)				
3.0	Carry out intake and overflow works as follows:-				
3.0.1	Perimeter grout collar around pond mouth/crest (300–450 mm wide, 150–200 mm thick; 1:3 cement: sand)	m ³	1		
3.0.2	Inlet energy dissipation (riprap apron on geotextile).	m ³	0.4		
3.0.3	Spillway/outlet protection (riprap)	m ³	0.4		



Fadhili Trust

P.O.Box 244 - 00511,

Ongata Rongai.

Tel: +254 710 401 208

+254 733 867 112

Email: info@fadhilitrust.org

Web: www.fadhilitrust.org

3.0.4	Construct a mass concrete foundation base using a concrete mix of 1:3:6 for the 2 No. Silt Traps of dimension 1.2m x 1.2m x 0.1m	m ³	0.15		
3.0.5	Provide materials and construct 2 No. Silt Traps Walling using 150mm thick approved stone; bedding, jointing, and pointing in cement sand (1:3) mortar and plaster 2 No. silt traps interior walling to 25mm thickness for the silt trap using a 1:3 mortar mix	m ²	5.76		
3.0.6	Provide and place Dia. 100mm uPVC pipes with galvanized mesh SCREEN (to sieve chaff) for inlets	m	4		
Sub Total (Carried to Collection)					
4.0	Contingencies				
4.01	Allow a provisional sum of Kshs. 2000 for contingencies on each farm pond	Nr.	1	2,000	2000
	Total Sum for 1 farm pond				
	Grand Total for 25 farm Ponds				
	VAT (16%)				
	Grand Total				

Disclaimer.

This is an invitation for quotation only, and Fadhili Trust reserves the right to cancel it at any time, with or without notice. In such cases, the organization shall accept no liability whatsoever. Only the successful bidder will be notified. If you do not receive email communication within a week after the submission deadline has expired, consider your bid unsuccessful.